

STEALTH

Semi-In Ground Pools



STEALTH POOL QUICK REFERENCE GUIDE



Welcome

Welcome to the Unique Pools and Spas Family! The following guide is to help you understand what is involved in building your new semi-inground pool.

Your Stealth pool installation requirements:

- 1. Mark the desired location of the pool and equipment**
- 2. Check with your local codes office for permits and other requirements**

Like any outdoor construction project, unforeseen circumstances may occur (weather, scheduling, ground conditions, etc.).

If you have any questions, at any point in the process, please reach out to us directly at:

Unique PSB of Orlando

2640 Mercy Dr.

Orlando, FL 32808

(407) 296-6776

Homeowner's Pre-Installation Checklist

- ☐ **Underground Lines:** Locate and clearly mark electric, phone, cable, or any other utility lines, septic tank, and field lines on or near pool site prior to excavation. Call 811 (free) and get reference number of 811 ticket for installation department. Note: Private utilities such as electrical lines to outbuildings, gas grills and light lines will not be marked by 811 and are the customer's responsibility to accurately mark their location. Unique PSB and Install team is not responsible for damage to unmarked utilities during the excavation or build process.
- ☐ **Permits/HOA:** Check with local, county, and state codes departments and provide any permits required to issue complete compliance with all code ordinances. If HOA approval is required, please attain approval.
- ☐ **Pool Plus Pump & Filter Location:** Locate and mark the pool site and filter location prior to excavation and in accordance with all state and local codes.
- ☐ **Identify Path Access:** Provide an 8' access path for excavation equipment. Unique PSB and install team will not be responsible for damage to the yard, driveway, or any obstacles in access path. We do not drive over septic or field lines.
- ☐ **Pump Electrical:** 110v 20 amp (plug) **OR** 220v 30 amp (hardwire).

Note: UNIQUE PSB IS NOT RESPONSIBLE FOR WATER REPLACEMENT FOR ANY REASON.

Note: You will need to schedule your electrical the day AFTER the pool is installed, NOT before.

Laying Out Your Pool

To begin, make sure that the pool site is not within 15' of any overhead power lines, and 10' from any trees. The pool cannot be built over any part of a septic system, and you are responsible for making sure the pool is not infringing on any property lines, easements, or built over any utility lines. We do our best to accommodate the customer's chosen site for the pool sometimes it does need to be moved once install team is on site and that will be at the discretion of the excavator.

Note: Required distances from property lines vary in every community. Most of this information can be obtained when you get your permit. Note any specific code/permit limitations (ex. distance from house, property line, etc.)

Round Pools: Once you have chosen your site, place a screwdriver into the ground at the center of the pool. Secondly, measure a section of string that is half of the diameter of your pool, plus an extra 2'. For example, a 24' pool would require a 14' string. The extra 2' is for the over dig of the pool site. We will need to have a minimum of 2' around the pool to have the room for proper installation. Next, tie one end of the string to the screwdriver, and while pulling the string tight, walk the circumference of the pool and mark it with several stakes or paint.

Oval Pools: Oval pools are done in about the same manner. Keep in mind that due to the side braces on an oval pool, the "overdig" requires the dimensions of the pool, plus 2' on the length and 2' on the width. For example, an 18' x 33' oval would be staked out at 20' x 35'. Stake out or paint the area as best you can, and the installer will verify and square up the site for you.

So remember these keys questions:

- Approximately how far out of level is the pool site (Inches)?
- Are there overhead power lines near the pool site?
- Are there underground utilities?
- Are there any trees or tree stumps near the pool site?
- Do you have a septic system?

Installation Photos

Most homeowners would like to know what their project will look like after installation. Below are some great photos of our installation and what to expect after the project is completed.



This is left over pool sand on the job site. It is more cost saving to order more sand and have a little left over than to order and pay another delivery charge if you don't have enough.



This pool had a very small slope, but you can see how much dirt is left behind. Additional excavation, grading and dirt work is available by bid only, made prior to install date, and paid directly to the excavator.



Some jobs have a little rock in the ground when we dig, so be aware that your yard could have the same. It is important for the bottom of the pool base around the outside to have dirt pushed up around it to help contain the sand.




This is a picture of your pump and filter. Notice the dirt ground after digging out the pool. This is very common, and most homeowners plant seed and straw to grow back the grass after installation, or you can use decorative gravel.



This picture shows where a homeowner asked us to move the dirt to the end of his property. This can be done by paying the excavator directly after the pool is installed. A local bobcat operator can be found to move dirt and grade your yard after the build for an affordable rate.

Filling Instructions

Pool liners are designed to stretch slightly as they fit the pool during filling. Weather conditions and air temperature directly affect the pace in which the filling can be completed. If the pool is filled at night, or too quickly during the day without sunlight reaching the pool, the liner can buckle the wall or pull down causing a sag in the wall pattern. These are not usually structural problems. However, they are unattractive. The installation guarantee does not cover the liner sags or wall buckles caused by improper filling. We have included detailed suggestions below to help prevent these issues from happening.



32-65 Degree Filling:

During the final stages of installation, the installers will begin to fill the pool to seat the liner. They will remove any folds from the packaging and position the liner evenly around the wall and floor. After the installers have left, continue filling the pool until you reach a total of 6 inches. Please do not continue to fill the remainder of the pool for the rest of the day. The following days if weather allows, begin to add 2 to 3 inches of water each day.

Special Instructions:

- A. Only add water on days that direct sunlight is reaching the pool.
- B. Do not add more than 3 inches unless the water is 65 degrees. If it is above 65 degrees and direct sunlight is reaching the pool, do not add more than 6 inches.
- C. Continue this process until you reach a total of 24 inches. After 24 inches you may fill the remainder of the pool. Only add water on the days that have direct sunlight reaching the pool.



65 Degrees & Warmer Filling:

During the final stages of installation, the installers will begin to fill the pool to seat the liner. They will remove the folds from the packaging and position the liner evenly around the wall and floor. After the installers have left, continue filling the pool until direct sunlight is no longer reaching the pool. Please DO NOT continue to fill the pool for the remainder of the day. The following day (if the sun allows), begin to add water as direct sunlight is reaching the pool each day.

Special Instructions:

- A. Only add water on days that have direct sunlight reaching the pool.
- B. If the temperature is above 65 degrees and direct sunlight is reaching the pool, you may continue filling the pool until direct sunlight is no longer reaching the pool.
- C. Continue this process until you reach a total of 24 inches. After reaching 24 inches, you may fill the remainder of the pool.

Additional Expenses

Services not provided by Unique PSB

Additional Install Expenses

- Electrical work for pump and filter package
- Water to fill the pool
- Hardscapes / Decking and Landscaping
- Permit (if required)

Potential Additional Install Expenses

- Dirt haul off if nowhere to stage dirt
- Electrical work to run lighting (In-Ground lighting)
- Backfilling around pool, this should be done after the build, but before the pool is filled
- Tree or stump removal
- Disassembling of an existing pool
- Moving an existing overhead power line or underground septic/field line
- Additional Plumbing line if pump & filter placement more than the 5 ft.
- Additional electric or gas line possible if purchasing a heater or heat pump
- A sump pump might be needed if there are heavy rains during or shortly after the pool build to remove the excess water around the pool location
- Fence costs
- If unable to access the yard with a concrete truck a concrete pump may be needed

YOU ARE NOW READY TO ENJOY THE SUMMER IN
THE SAFETY AND COMFORT OF YOUR VERY OWN POOL!



On behalf of everyone at Unique PSB, we would like to take a moment to thank you for choosing us to be your swimming pool dealership. The building of a Stealth swimming pool can be an exciting and quick process.

